

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE*

FORM APPROVED
OMB NO. 1040-0136
Expires: February 28, 1995

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

TYPE OF WORK DRILL <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. UTU-73456
TYPE OF WELL <input type="checkbox"/> OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE		6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A
2. NAME OF OPERATOR QEP UINTA BASIN, INC.		7. UNIT AGREEMENT NAME BIG VALLEY UNIT # UTU-81308X
3. ADDRESS 11002 E. 17500 S. Vernal, Ut 84078		8. FARM OR LEASE NAME, WELL NO. RWS 12ML-6-9-24
4. LOCATION OF WELL (Report location clearly and in accordance with and State requirements*) At Surface 648160X 2180' FSL 698' FWL, NWSW, SECTION 6, T9S, R24E At proposed production zone 44360654 40.063715 -109.262759		9. API NUMBER: 4304737312
14. DISTANCE IN MILES FROM NEAREST TOWN OR POSTOFFICE* 38 +/- SOUTHEAST OF VERNAL, UTAH		10. FIELD AND POOL, OR WILDCAT UNDESIGNATED
15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (also to nearest drig, unit line if any) 698' +/-	16. NO. OF ACRES IN LEASE 1239.79	11. SEC., T, R, M, OR BLK & SURVEY OR AREA SEC. 6, T9S, R24E Mer SLB
18. DISTANCE FROM PROPOSED location to nearest well, drilling, completed, applied for, on this lease, ft 2250' +/-	19. PROPOSED DEPTH 9000'	12. COUNTY OR PARISH Uintah
21. ELEVATIONS (Show whether DF, RT, GR, ect.) 5037.4' GR	22. DATE WORK WILL START ASAP	13. STATE UT
24. Attachments		17. NO. OF ACRES ASSIGNED TO THIS WELL 40
		20. BLM/BIA Bond No. on file ESB000024
		23. Estimated duration 10 days

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan
3. A surface Use Plan (if location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an exisiting bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

SIGNED

Jan Nelson

Name (printed/typed) Jan Nelson

DATE 10-20-05

TITLE

Regulatory Affairs

(This space for Federal or State office use)

PERMIT NO.

43-047-37312

APPROVAL DATE

Application approval does not warrant or certify the applicant holds any legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

Bradley G. Hill

TITLE

BRADLEY G. HILL
ENVIRONMENTAL SCIENTIST III

*See Instructions On Reverse Side

The 18 U.S.C Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

Federal Approval of this
Action is Necessary

RECEIVED

OCT 24 2005
11-14-05
DIV. OF OIL, GAS & MINING

CONFIDENTIAL

T9S, R24E, S.L.B.&M.

QUESTAR EXPLR. & PROD.


Well location, RWS #12ML-6-9-24, located as shown in the NW 1/4 SW 1/4 of Section 6, T9S, R24E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 45EAM LOCATED IN THE NW 1/4 SW 1/4 OF SECTION 6, T9S, R24E, S.L.B.&M. TAKEN FROM THE BONANZA, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5350 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert J. Hay

REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 09-15-05	DATE DRAWN: 10-06-05
PARTY D.A. C.R. L.K.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE QUESTAR EXPLR. & PROD.	



LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.
- △ = TRUE POSITION

(NAD 83)
LATITUDE = 40°03'49.48" (40.063744)
LONGITUDE = 109°15'48.62" (109.263506)
(NAD 27)
LATITUDE = 40°03'49.60" (40.063778)
LONGITUDE = 109°15'46.18" (109.262828)

Additional Operator Remarks

QEP Uinta Basin, Inc. proposes to drill a well to 9000' to test the MesaVerde. If productive, casing will be run and the well completed. If dry, the well will be plugged and abandoned as per BLM and State of Utah requirements"

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 and 24 East.

See attached Onshore No. 1

See attached notice of intent to complete into multiple pools.

Please be advised that QEP Uinta Basin Inc. agrees to be responsible under the terms and conditions of the lease for the operations conducted upon the lease lands.

Bond coverage for this well is provided by Bond No.ESB000024. The principal is QEP Uinta Basin Inc. via surety as consent as provided for the 43 CFR 3104.2.

NOTICE OF INTENT TO COMPLETE INTO MULTIPLE POOLS

RWS 12ML-6-9-24

In compliance with the stated objectives of section R649-3-22 of the Utah Administrative Code and the Utah Oil and Gas Conservation Act, Questar Exploration and Production Company hereby requests the commingling of production between intervals in the RWS 12ML-6-9-24. Questar considers this commingling to be in the public interest in that it promotes maximum ultimate economic recovery, prevents waste, provides for orderly and efficient production of oil and gas and presents no detrimental effects from commingling the two gas streams.

Questar requests approval for the commingling between the Mesa Verde and Wasatch intervals. As the well is not in a Unit PA and the ownership is the same between formations, production will be reported as combined Mesa Verde / Wasatch production.

This well will be completed using multiple stage hydraulic fracturing. Bridge plugs will be used to isolate completion intervals during fracturing operations and will be drilled up prior to putting the well on production. Mesa Verde and Wasatch intervals will be fractured separately, except where they occur too close together to make isolation unfeasible.

A plat of all contiguous owners will follow along with an affidavit stating that all contiguous owners have been notified and given a 15 day objection period.

I hereby certify that the foregoing is true and correct

A handwritten signature in black ink, appearing to read "Mike Stahl", written in a cursive style.

Mike Stahl
Completion Engineer
Questar Exploration & Production

AFFIDAVIT OF NOTICE

STATE OF COLORADO)
COUNTY OF DENVER) ss:

Angela Page, being duly sworn, deposes and says:

1. That I am employed by Questar Market Resources in the capacity as a Landman. My business address is Independence Plaza
1050 17th Street, Suite 500
Denver, CO 80265
2. In my capacity as a Landman, pursuant to the provisions of Utah Administrative Rule 615-3-22 I have provided a copy of Questar Market Resource's application for completion of the RWS 12ML-6-9-24 well into two or more pools, in the form of Utah Division of Oil, Gas and Mining's Form 9 Sundry Notice, to owners of all contiguous oil and gas leases or drilling units overlying the pools which are the subject of that application.
3. In my capacity as a Landman I am authorized to provide such notice of Questar Market Resource's application to contiguous owners and to make this affidavit on this 27th day of July, 2005.


Angela Page


Printed Name: Angela Page

The foregoing instrument was sworn to and subscribed before me this 27th day of July, 2005, by Angela Page


Heather Lang
Notary Public

My Commission Expires 07/08/2008






Sec 6, T9S-R24E



40-acre pool



Commingled well



Big Valley Unit boundary



Lease line

Tw / Kmv COMMINGLED PRODUCTION

Uinta Basin—Uintah County, Utah

**Wells: RWS 2ML-6-9-24,
RWS 4ML-6-9-24, RWS 6ML-6-9-24,
RWS 8ML-6-9-24, RWS 12ML-6-9-24,
RWS 14ML-6-9-24, RWS 16ML-6-9-24
Lease: UTU-73456**

QUESTAR
Exploration and
Production

1050 17th St., # 500 Denver, CO 80202

Geologist: JD Herman

Engineer:

Date: August 16, 2005

Landman: Angela Page

Technician:

05722MapaUtah.mpaComm 2009060924.cdr

Qep Uinta Basin, Inc.
RWS 12ML-6-9-24

ONSHORE OIL & GAS ORDER NO. 1
Approval of Operations on Onshore
Federal Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

1. Formation Tops

The estimated tops of important geologic markers are as follows:

Formation	Depth
Uinta	Surface
Green River	1630'
Wasatch	4370'
Mesa Verde	6280'
TD	9000'

2. Anticipated Depths of Oil, Gas, Water and Other Mineral Bearing Zones

The estimated depths at which the top and bottom of the anticipated water, oil, gas or other mineral bearing formations are expected to be encountered are as follows:

Substance	Formation	Depth
Oil/Gas	Mesa Verde	9000'

All fresh water and prospectively valuable minerals encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

All water shows and water-bearing sands will be reported to the BLM in Vernal, Utah. Copies of State of Utah form OGC-8-X are acceptable. If no flows are detected, samples will be submitted to the BLM along with any water analyses conducted.

3. Anticipated Bottom Hole Pressures

Maximum anticipated bottom hole pressure equals approximately 3903.0 psi.

**QEP UINTA BASIN, INC.
RWS 12ML-6-9-24
2180' FSL 698' FWL
NWSW, SECTION 6, T9S, R24E
UINTAH COUNTY, UTAH
LEASE # UTU-73456**

ONSHORE ORDER NO. 1

MULTI – POINT SURFACE USE & OPERATIONS PLAN

An onsite inspection was conducted for the RWS 12ML-6-9-24 on October 12, 2005. Weather conditions were clear and sunny at the time of the onsite. In attendance at the inspection were the following individuals:

Paul Buhler	Bureau of Land Management
Todd McGrath	Bureau of Land Management
Jan Nelson	QEP Uinta Basin Inc.

1. Existing Roads:

The proposed well site is approximately 38 miles southeast of Vernal, Utah.

Refer to Topo Maps A and B for location of access roads within a 2 – mile radius.

There will be improvements made to existing two track County road.

2. Planned Access Roads:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 to 24 East.

Refer to Topo Map B for the location of the proposed access road.

3. Location of Existing Wells Within a 1 – Mile Radius:

Please refer to Topo Map C.

4. Location of Existing & Proposed Facilities:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 to 24 East.

Refer to Topo Map D for the location of the proposed pipeline.

QEP requests a surface pipeline based on the following justification included in the attached "Request for Exception".

5. Location and Type of Water Supply:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated

fields in Townships 07 and 08 South, Ranges 21 to 24 East.

6. Source of Construction Materials:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 to 24 East.

7. Methods of Handling Waste Materials:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 to 24 East.

8. Ancillary Facilities:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 to 24 East.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

A pit liner is required. A felt pit liner will be required if bedrock is encountered.

10. Plans for Reclamation of the Surface:

Please see QEP Uinta Basin, Inc. Standard Operating Practices for Mesa Verde Formation Wells located in Red Wash, Wonsits Valley, Gypsum Hills, White River, Glen Bench, and undesignated fields in Townships 07 and 08 South, Ranges 21 to 24 East.

Interim Reclamation

Please see attached Interim Reclamation plan.

Once the well is put onto production, QEP will reclaim as much of the well pad as possible that will allow for operations to continue in a safe and reasonable manner. Reseeding will be done in the spring or fall of every year to allow winter precipitation to aid in the success of reclamation.

Seed Mix:

Interim Reclamation:

9 lbs Hycrest Crested Wheatgrass

3 lbs Forage Kochia

Final Reclamation:

Seed Mix # 1 3 lbs. Fourwing Saltbush, 4 lbs. Hycrest Crested Wheat Grass, 1 lbs. Needle & Thread Grass and 3 lbs. Indain Rice Grass.

11. Surface Ownership:

Bureau of Land Management

170 South 500 East

Vernal, Utah 84078

(435) 781-4400

12. Other Information

A Class III archaeological survey was conducted by Montgomery Archaeology Consultants. A copy of this report was submitted directly to the appropriate agencies by Montgomery Archaeology Consultants. Cultural resource clearance was recommended for this location.

A class III paleontological survey was conducted by Intermountain Paleo Consulting. A copy of this report was submitted directly to the appropriate agencies by Stephen D. Sandau. The inspection resulted in the location of no fossil resources. However, if vertebrate fossil(s) are found during construction a paleontologist should be immediately notified. QEP will provide paleo monitor if needed.

No drilling or construction will take place during the Pronghorn season May 10 thru June 20th.

There is a Ferrit Stipulation from March 1st to July 15th. No construction or drilling will commence during this period unless otherwise determined by a wildlife biologist that the site is inactive.

There is a Burrowing Owl Stipulation from April 1st to August 15th. No construction or drilling will commence during this period unless otherwise determined by a wildlife biologist that the site is inactive.

QEP Uinta Basin, Inc.
Request for Exception to Buried Pipeline
for
RWS 12ML-6-9-24

QEP respectfully requests an exception to burying this pipeline. We understand the standard Condition of Approval (COA) that may be included in the approved Application for Permit to Drill (APD) is: *"As a Best Management Practice (BMP), the pipeline would be buried within the identified construction width of an access corridor that contains the access road and pipelines. The construction width for the access corridor would increase from 30 feet, by an additional 20 feet, to a total of 50 feet. Exceptions to this BMP may be granted where laterally extensive, hard indurated bedrock, such as sandstone, is at or within 2 feet of the surface; and, soil types with a poor history of successful rehabilitation."* QEP will install the pipeline within the access corridor and will avoid cross-country installation when possible. Our reason for requesting a surface line is based on the following justification:

Class IV VRM

- ♦ This area's designated Visual Resource Management is classified as Class IV. The Class IV objective is to provide for management activities that require major modification to the existing character of the landscape. The level of change to the landscape can be high. The management activities may dominate the view and may be the major focus of the viewer attention. However, every attempt should be made to minimize the impact of these activities through careful location, minimal disturbance, and repetition of the basic visual elements of form, line, color, and texture.
- ♦ QEP feels that surface pipe will comply with this classification more so than buried pipe due to the amount of surface disturbance that will be required to bury it. We believe surface installation within the access corridor will minimize the disturbance so that the pipeline does not dominate the view.

Environmental and Safety Concerns

- ♦ Buried pipe will greatly increase surface disturbance and habitat fragmentation. The soil in this area has a poor history of successful rehabilitation. Buried pipe will have an increased corrosion rate and would need to be dug up for repairs or replacement; the constant surface disturbance will not allow time for successful reclamation.
- ♦ Increasing surface disturbance will greatly increase noxious and invasive weed infestation.

- ♦ With the increased corrosion rate, buried pipe may have undetectable leaks that could go unnoticed for months. Small leaks may turn into large plumes of underground hazards because they are not easily monitored and not seen right away. An undetected leak also increases the potential for explosive incidents. Once detected, the surface will need to be disturbed, once again, to dig up the line and replace or repair it.
- ♦ Accidents associated with pipe breaks during construction activities could increase substantially as the number of buried lines increases.
- ♦ The additional surface disturbance will increase the risk of disturbing paleontological sites.

Operational and Mechanical Concerns for Gas Lines

- ♦ Cathodic protection will be required for buried pipe. Cathodic protection requires anode beds that must be maintained. This will add substantial costs in labor and material. Additional power lines will need to be installed to the anode beds. The additional costs for equipment and labor will be approximately \$50,000.00 per section.
- ♦ Pipeline markers need to be used with buried pipe. This will add costs in labor and material.
- ♦ Every tie in requires a valve. The average distance between valves is approximately ¼ mile. Valves will have to be placed in “freeze boxes” or “valve boxes”. Valve boxes will be considered confined space which increases the manpower needed to repair or replace valves. Every valve box will also require bright yellow guard rails.
- ♦ Additional equipment required for buried pipe can include blades/dozers, trenchers (cutting or blasting in hard rock), side booms, etc. which increases installation costs.
- ♦ Buried pipe must have fusion bonded epoxy (FBE) coating. FBE pipe will cost an additional \$2.00 per foot compared to bare pipe.
- ♦ This pipeline has the potential for being upgraded/upsized to a larger pipe diameter depending on production volumes. If upsizing is required, the pipe will need to be dug up which will cause additional surface disturbance and will not allow adequate time for successful reclamation.
- ♦ Surface lines are sometimes relocated to accommodate new locations; this is done in an effort to minimize the amount of pipe needed and the amount of surface disturbed. If this pipe is buried, this will no longer be an option.

Lessee's or Operator's Representative:

Jan Nelson
Red Wash Rep.
QEP Uinta Basin, Inc.
11002 East 17500 South
Vernal, Utah 84078
(435) 781-4331


Certification:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil & Gas Orders, the approved plan of operations, and any applicable Notice to Lessees.

QEP Uinta Basin Inc. will be fully responsible for the actions of their subcontractors.

A complete copy of the approved Application for Permit to Drill will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by QEP Uinta Basin, Inc. its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.



Jan Nelson
Red Wash Representative

20-Oct-05

Date

QUESTAR EXPLR. & PROD.

RWS #12ML-6-9-24

LOCATED IN UINTAH COUNTY, UTAH
SECTION 6, T9S, R24E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY



- Since 1964 -

UELS Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


10 06 05
MONTH DAY YEAR

PHOTO

TAKEN BY: D.A. DRAWN BY: L.K. REVISED: 00-00-00

FIGURE #1

2180 FSL 698' FWL



QUESTAR EXPLR. & PROD.

FIGURE #2

TYPICAL CROSS SECTIONS FOR

RWS #12ML-6-9-24


SECTION 6, T9S, R24E, S.L.B.&M.

2180 FSL 698' FWL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 10-06-05

Drawn By: L.K.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

CUT

(6") Topsoil Stripping = 1,740 Cu. Yds.

Remaining Location = 7,250 Cu. Yds.

TOTAL CUT = 8,990 CU.YDS.

FILL = 5,810 CU.YDS.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION


Excess Material = 3,180 Cu. Yds.

Topsoil & Pit Backfill = 3,180 Cu. Yds.
(1/2 Pit Vol.)

EXCESS UNBALANCE = 0 Cu. Yds.
(After Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017



LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD
- EXISTING 2-TRACK NEEDS UPGRADED

QUESTAR EXPLR. & PROD.

RWS #12ML-6-9-24
SECTION 6, T9S, R24E, S.L.B.&M.
2180' FSL 698' FWL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
MAP

10 06 05
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: L.K. REVISED: 00-00-00

B
TOPO



LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- ⊖ SHUT IN WELLS
- ⊗ WATER WELLS
- ⊖ ABANDONED WELLS
- ⊖ TEMPORARILY ABANDONED

QUESTAR EXPLR. & PROD.

RWS #12ML-6-9-24
SECTION 6, T9S, R24E, S.L.B.&M.
2180' FSL 698' FWL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813




**TOPOGRAPHIC
MAP**

10 06 05
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: L.K. REVISED: 00-00-00





APPROXIMATE TOTAL PIPELINE DISTANCE = 2893' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)

QUESTAR EXPLR. & PROD.

RWS #12ML-6-9-24
SECTION 6, T9S, R24E, S.L.B.&M.
2180' FSL 698' FWL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC
MAP

10 06 05
MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: L.K. REVISED: 00-00-00

D
TOPO

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 10/25/2005

API NO. ASSIGNED: 43-047-37312

WELL NAME: RWS 12ML-6-9-24

OPERATOR: QEP UINTA BASIN, INC. (N2460)

CONTACT: JAN NELSON

PHONE NUMBER: 435-781-4331

PROPOSED LOCATION:

NWSW 06 090S 240E

SURFACE: 2180 FSL 0698 FWL

BOTTOM: 2180 FSL 0698 FWL

UINTAH

UNDESIGNATED (2)

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-73456

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DEN	11/19/05
Geology		
Surface		

LATITUDE: 40.06372

LONGITUDE: -109.2628

RECEIVED AND/OR REVIEWED:


☒ Plat
☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. ESB000024)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 43-8496)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)
(Wasatch, Mesa Verde)

LOCATION AND SITING:

_____ R649-2-3.
Unit BIG VALLEY
☒ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
_____ R649-3-3. Exception
_____ Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
_____ R649-3-11. Directional Drill

COMMENTS: Sop, Separate file

STIPULATIONS: 1- Federal approved
2- Spacing Strip
3- Commingle



OPERATOR: QEP UINTA BASIN INC (N2460)

SEC: 5,6 T. 9S R. 24E

FIELD: UNDESIGNATED (002)

COUNTY: UNITAH

SPACING: R649-3-2 / GENERAL SITING

Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NE PP OIL
- NE SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 26-OCTOBER-2005

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

October 26, 2005

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2005 Plan of Development Big Valley Unit, Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2005 within the Big Valley, Uintah County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ Wasatch-MesaVerde)		
43-047-37306	RWS 2ML-5-9-24 Sec 5	T09S R24E 0774 FNL 1942 FEL
43-047-37307	RWS 8ML-5-9-24 Sec 5	T09S R24E 1895 FNL 0467 FEL
43-047-37308	RWS 10ML-5-9-24 Sec 5	T09S R24E 1785 FSL 2169 FEL
43-047-37309	RWS 12ML-5-9-24 Sec 5	T09S R24E 2056 FSL 0851 FWL
43-047-37310	RWS 14ML-5-9-24 Sec 5	T09S R24E 0860 FSL 1784 FWL
43-047-37311	RWS 16ML-5-9-24 Sec 5	T09S R24E 0823 FSL 0824 FEL
43-047-37312	RWS 12ML-6-9-24 Sec 6	T09S R24E 2180 FSL 0698 FWL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File – Big Valley Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:10-26-05



State of Utah

Department of Natural Resources

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas & Mining

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

November 14, 2005

QEP Uinta Basin, Inc.
11002 E 17500 S
Vernal, UT 84078

Re: RWS 12ML-6-9-24 Well, 2180' FSL, 698' FWL, NW SW, Sec. 6, T. 9 South,
R. 24 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Administrative approval for commingling the production from the Wasatch formation and the Mesaverde formation in this well is hereby granted. Appropriate information has been submitted to DOGM in accordance with R649-3-22. No written objections from owners were received by DOGM.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-37312.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: QEP Uinta Basin, Inc.

Well Name & Number RWS 12ML-6-9-24

API Number: 43-047-37312

Lease: UTU-73456

Location: NW SW Sec. 6 T. 9 South R. 24 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

OCT 20 2005
SUBMIT IN TRIPlicate

FORM APPROVED
OMB NO. 1040-0136
Expires: February 28, 1995

BLM VERNAL, UTAH

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

TYPE OF WORK

DRILL ☒

DEEPEN ☐

TYPE OF WELL

☐

☒

☐

SINGLE ☒

MULTIPLE ☐

OIL WELL

GAS WELL

OTHER

ZONE

ZONE

2. NAME OF OPERATOR

QEP UINTA BASIN, INC.

Contact: Jan Nelson

E-Mail: jan.nelson@questar.com

3. ADDRESS

11002 E. 17500 S. Vernal, Ut 84078

Telephone number

Phone 435-781-4331 Fax 435-781-4323

4. LOCATION OF WELL (Report location clearly and in accordance with and State requirements*)

At Surface

2180' FSL 698' FWL, NWSW, SECTION 6, T9S, R24E

At proposed production zone

Lot 6

14. DISTANCE IN MILES FROM NEAREST TOWN OR POSTOFFICE*

38 +/- SOUTHEAST OF VERNAL, UTAH

15. DISTANCE FROM PROPOSED LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.

(also to nearest drig, unit line if any)

698' +/-

16. NO. OF ACRES IN LEASE

1239.79

18. DISTANCE FROM PROPOSED location to nearest well, drilling,
completed, applied for, on this lease, ft

2250' +/-

19. PROPOSED DEPTH

9000'

21. ELEVATIONS (Show whether DF, RT, GR, ect.)

5037.4' GR

22. DATE WORK WILL START

ASAP

17. NO. OF ACRES ASSIGNED TO THIS WELL

40

20. BLM/BIA Bond No. on file
ESB000024

23. Estimated duration

10 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan
3. A surface Use Plan (if location is on National Forest System Lands,
the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see
Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the
authorized officer.

SIGNED

Jan Nelson

Name (printed/typed) Jan Nelson

DATE 10-20-05

TITLE

Regulatory Affairs

(This space for Federal or State office use)

Accepted by the
Utah Division of
Oil, Gas and Mining

FOR RECORD ONLY

APPROVAL DATE

PERMIT NO.

Application approval does not warrant or certify the applicant holds any legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED

Mark R. Clavens

TITLE

Assistant Field Manager

Mineral Resources

DATE

03/07/2006

*See Instructions On Reverse Side

NOTICE OF APPROVAL

The 18 U.S.C Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the

United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

CONDITIONS OF APPROVAL ATTACHED

CONFIDENTIAL


RECEIVED
MAR 13 2006

Div. of OIL, GAS & MINING



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East VERNAL, UT 84078 (435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: QEP Uinta Basin
Well No: RWS 12ML-6-9-24
API No: 43-047-37312

Location: Lot 6, Sec. 6, T9S, R24E
Lease No: UTU-73456
Agreement: Big Valley Unit

Petroleum Engineer:	Matt Baker	Office: 435-781-4490	Cell: 435-828-4470
Petroleum Engineer:	Michael Lee	Office: 435-781-4432	Cell: 435-828-7875
Supervisory Petroleum Technician:	Jamie Sparger	Office: 435-781-4502	Cell: 435-828-3913
Environmental Scientist:	Paul Buhler	Office: 435-781-4475	Cell: 435-828-4029
Environmental Scientist:	Karl Wright	Office: 435-781-4484	
Natural Resource Specialist:	Holly Villa	Office: 435-781-4404	
Natural Resource Specialist:	Melissa Hawk	Office: 435-781-4476	
After hours contact number: (435) 781-4513		FAX: (435) 781-4410	

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a one-year period. An additional year extension may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

- | | |
|-------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|
| Location Construction
(Notify Paul Buhler) | - Forty-Eight (48) hours prior to construction of location and access roads. |
| Location Completion
(Notify Paul Buhler) | - Prior to moving on the drilling rig. |
| Spud Notice
(Notify Petroleum Engineer) | - Twenty-Four (24) hours prior to spudding the well. |
| Casing String & Cementing
(Notify Jamie Sparger SPT) | - Twenty-Four (24) hours prior to running casing and cementing all casing strings. |
| BOP & Related Equipment Tests
(Notify Jamie Sparger SPT) | - Twenty-Four (24) hours prior to initiating pressure tests. |
| First Production Notice
(Notify Petroleum Engineer) | - Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days. |

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- Conditions for Approval are in the APD or SOP
- The buried pipeline exception request has been received. It has been determined that the pipeline route has bedrock exposed at the surface. The exception is granted for a surface pipeline. Since the exception is granted the pipeline will be laid on the surface and a monitoring the line for paleo material would not be necessary.
- If paleontologic materials are uncovered during construction, the operator shall immediately stop work that might further disturb such materials and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation will be necessary for the discovered paleontologic material.

DOWNHOLE CONDITIONS OF APPROVAL

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

SITE SPECIFIC DOWNHOLE CONDITIONS OF APPROVAL

- The operator's proposed BOPE of 3M (for TD < 9500' per SOP) is acceptable at TD 9000 ft, bhp 3903 psi (gradient of 0.40 psi/ft), mud weight 10.5 ppg or under. Note that should bhp and downhole conditions warrant drilling with mud weights of 11.0 ppg or greater, a upgrade of the BOPE to a 5M system is required.

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well. Any changes in operation must have prior approval from the BLM, Vernal Field Office Petroleum Engineers.
- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- **Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.**
- Blowout prevention equipment (BOPE) will remain in use until the well is completed or abandoned. Closing unit controls must remain unobstructed and readily accessible at all times. Choke manifolds must be located outside of the rig substructure.
- All BOPE components will be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests must be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test must be reported in the driller's log.
- BOP drills must be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- All shows of fresh water and minerals will be reported and protected. A sample will be taken of any water flows and a water analysis furnished the BLM, Vernal Field Office. All oil and gas shows will be adequately tested for commercial possibilities, reported, and

protected.

- No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the BLM, Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM, Vernal Field Office must be obtained and notification given before resumption of operations.
- Chronologic drilling progress reports must be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- Any change in the program must be approved by the BLM, Vernal Field Office. "Sundry Notices and Reports on Wells" (Form BLM 3160-5) must be filed for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.
- Emergency approval may be obtained orally, but such approval does not waive the written report requirement. Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, will require the filing of a suitable plan pursuant to Onshore Oil & Gas Order No. 1 of 43 CFR 3164.1 and prior approval by the BLM, Vernal Field Office.
- In accordance with 43 CFR 3162.4-3, this well must be reported on the "Monthly Report of Operations" (Oil and Gas Operations Report ((OGOR)) starting with the month in which operations commence and continue each month until the well is physically plugged and abandoned. This report shall be filed in duplicate, directly with the Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217-0110, or call 1-800-525-7922 (303) 231-3650 for reporting information.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) will be submitted only when requested by the BLM, Vernal Field Office.
- **Please submit an electronic copy of all logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM. The cement bond log must be submitted in raster format (TIF, PDF other).**
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the BLM, Vernal Field Office.
- All measurement points shall be identified as point of sales or allocation for royalty

determination prior to the installation of facilities.

- Oil and gas meters will be calibrated in place prior to any deliveries. The Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the BLM, Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM, Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- This APD is approved subject to the requirement that, should the well be successfully completed for production, the BLM, Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location ($\frac{1}{4}$ Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and / or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas will be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from Field Office Petroleum Engineers.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events as defined in NTL3A, will be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water

analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.

- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, re-enter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-73456
2. NAME OF OPERATOR: QEP UINTA BASIN, INC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 11002 E. 17500 S. CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: BIG VALLEY UNIT #UTU-81308X
PHONE NUMBER: (435) 781-4331		8. WELL NAME and NUMBER: RWS 12ML-6-9-24
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2180' FSL 698' FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 6 9S 24E		9. API NUMBER: 4304737312
		10. FIELD AND POOL, OR WILDCAT: UNDESIGNATED
		COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>APD EXTENSION</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

QEP Uinta Basin, Inc. hereby requests a 1 year extension on the RWS 12ML-6-9-24.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 11-14-06
By: [Signature]

COPY SENT TO OPERATOR
Date: 11-15-06
Initials: RM

NAME (PLEASE PRINT) Jan Nelson	TITLE Regulatory Affairs
SIGNATURE [Signature]	DATE 11/10/2006

(This space for State use only)

RECEIVED

NOV 13 2006

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-37312
Well Name: RWS 12ML-6-9-24
Location: 2180' FSL 698' FWL, NWSW, SEC. 6 T9S R24E.
Company Permit Issued to: QEP UINTA BASIN, INC.
Date Original Permit Issued: 11/14/2005

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

11/10/2006

Date

Title: REGULATORY AFFAIRS

Representing: QEP UINTA BASIN, INC.

RECEIVED

NOV 13 2006

DIV. OF OIL, GAS & MINING

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

Change of Operator (Well Sold)

X - Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/1/2007

FROM: (Old Operator): N2460-QEP Uinta Basin, Inc. 1050 17th St, Suite 500 Denver, CO 80265 Phone: 1 (303) 672-6900	TO: (New Operator): N5085-Questar E&P Company 1050 17th St, Suite 500 Denver, CO 80265 Phone: 1 (303) 672-6900
-------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------

CA No.				Unit:		BIG VALLEY UNIT				
WELL NAME				SEC TWN RNG		API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LISTS							*			

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 4/19/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 4/16/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 1/31/2005
- Is the new operator registered in the State of Utah: Business Number: 764611-0143
- (R649-9-2) Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: n/a
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 4/23/2007 BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: 4/23/2007
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: _____
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 4/30/2007 and 5/15/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 4/30/2007 and 5/15/2007
- Bond information entered in RBDMS on: 4/30/2007 and 5/15/2007
- Fee/State wells attached to bond in RBDMS on: 4/30/2007 and 5/15/2007
- Injection Projects to new operator in RBDMS on: 4/30/2007 and 5/15/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: ESB000024
- Indian well(s) covered by Bond Number: 799446
- (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 965003033
- The **FORMER** operator has requested a release of liability from their bond on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS: THIS IS A COMPANY NAME CHANGE.

SOME WELL NAMES HAVE BEEN CHANGED AS REQUESTED

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)
BIG VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
RWS 3ML-9-9-24	RWS 3ML-9-9-24	NENW	09	090S	240E	4304735483	15190	Federal	GW	S
RWS 10ML-6-9-24	RWS 10ML-6-9-24	NWSE	06	090S	240E	4304735653	15333	Federal	GW	P
CWD 4ML-32-8-24	CWD 4ML-32-8-24	NWNW	32	080S	240E	4304735684	14288	Federal	GW	P
NBZ 4ML-30-8-24	NBZ 4D-30-8-24	NWNW	30	080S	240E	4304737229		Federal	GW	APD
NBZ 6ML-30-8-24	NBZ 6ML-30-8-24	SENE	30	080S	240E	4304737230		Federal	GW	APD
NBZ 8ML-30-8-24	NBZ 8ML-30-8-24	SENE	30	080S	240E	4304737231	15976	Federal	GW	DRL
NBZ 10ML-30-8-24	NBZ 10ML-30-8-24	NWSE	30	080S	240E	4304737232		Federal	GW	APD
NBZ 12ML-30-8-24	NBZ 12D-30-8-24	NWSW	30	080S	240E	4304737233		Federal	GW	APD
NBZ 14ML-30-8-24	NBZ 14ML-30-8-24	SESW	30	080S	240E	4304737234		Federal	GW	APD
NBZ 6ML-31-8-24	NBZ 6D-31-8-24	SENE	31	080S	240E	4304737235		Federal	GW	APD
NBZ 4ML-31-8-24	NBZ 4D-31-8-24	NWNW	31	080S	240E	4304737236		Federal	GW	APD
NBZ 13ML-29-8-24	NBZ 13ML-29-8-24	SWSW	29	080S	240E	4304737237	15954	Federal	GW	DRL
NBZ 8ML-31-8-24	NBZ 8D-31-8-24	SENE	31	080S	240E	4304737238		Federal	GW	APD
NBZ 2ML-31-8-24	NBZ 2ML-31-8-24	NWNE	31	080S	240E	4304737239		Federal	GW	APD
NBZ 11ML-29-8-24	NBZ 11D-29-8-24	NESW	29	080S	240E	4304737240		Federal	GW	APD
NBZ 5ML-29-8-24	NBZ 5D-29-8-24	SWNW	29	080S	240E	4304737241		Federal	GW	APD
NBZ 7ML-29-8-24	NBZ 7ML-29-8-24	SWNE	29	080S	240E	4304737243		Federal	GW	APD
NBZ 9ML-29-8-24	NBZ 9D-29-8-24	NESE	29	080S	240E	4304737244		Federal	GW	APD
NBZ 15ML-29-8-24	NBZ 15ML-29-8-24	SWSE	29	080S	240E	4304737246		Federal	GW	APD
CWD 3ML-32-8-24	CWD 3ML-32-8-24	NENW	32	080S	240E	4304737274		Federal	GW	APD
CWD 8ML-32-8-24	CWD 8ML-32-8-24	SENE	32	080S	240E	4304737275		Federal	GW	APD
CWD 12ML-32-8-24	CWD 12ML-32-8-24	NWSW	32	080S	240E	4304737276	15323	Federal	GW	S
CWD 14ML-32-8-24	CWD 14ML-32-8-24	SESW	32	080S	240E	4304737277		Federal	GW	APD
CWD 16ML-32-8-24	CWD 16D-32-8-24	SESE	32	080S	240E	4304737278		Federal	GW	APD
RWS 2ML-5-9-24	RWS 2ML-5-9-24	NWNE	05	090S	240E	4304737306	15925	Federal	GW	DRL
RWS 8ML-5-9-24	RWS 8D-5-9-24	SENE	05	090S	240E	4304737307		Federal	GW	APD
RWS 10ML-5-9-24	RWS 10ML-5-9-24	NWSE	05	090S	240E	4304737308	15787	Federal	GW	P
RWS 12ML-5-9-24	RWS 12ML-5-9-24	NWSW	05	090S	240E	4304737309	15481	Federal	GW	P
RWS 14ML-5-9-24	RWS 14D-5-9-24	SESW	05	090S	240E	4304737310		Federal	GW	APD
RWS 16ML-5-9-24	RWS 16ML-5-9-24	SESE	05	090S	240E	4304737311		Federal	GW	APD
RWS 12ML-6-9-24	RWS 12ML-6-9-24	NWSW	06	090S	240E	4304737312	15947	Federal	GW	DRL
RWS 16ML-6-9-24	RWS 16ML-6-9-24	SESE	06	090S	240E	4304737335	15788	Federal	GW	DRL
CWD 1ML-32-8-24	CWD 1ML-32-8-24	NENE	32	080S	240E	4304737346		Federal	GW	APD
CWD 10ML-32-8-24	CWD 10D-32-8-24	NWSE	32	080S	240E	4304737347		Federal	GW	APD
RWS 6D-5-9-24	RWS 6D-5-9-24	SENE	05	090S	240E	4304737350		Federal	GW	APD
RWS 4ML-5-9-24	RWS 4ML-5-9-24	NWNW	05	090S	240E	4304737351	16020	Federal	GW	DRL
RWS 8D-6-9-24	RWS 8D-6-9-24	SENE	06	090S	240E	4304737352	15858	Federal	GW	DRL
RWS 2ML-6-9-24	RWS 2D-6-9-24	NWNE	06	090S	240E	4304737411		Federal	GW	APD
RWS 4ML-6-9-24	RWS 4ML-6-9-24	NWNW	06	090S	240E	4304737412	16035	Federal	GW	DRL
RWS 6D-6-9-24	RWS 6D-6-9-24	SENE	06	090S	240E	4304737413	99999	Federal	GW	DRL
RWS 14ML-6-9-24	RWS 14D-6-9-24	SESW	06	090S	240E	4304737414		Federal	GW	APD

QEP Uinta Basin (N2460) to QUESTAR E and P (N5085)
BIG VALLEY UNIT

4/30/2007 and 5/15/2007

Original Well Name	Well Name & No.	Q/Q	SEC	TWP	RNG	API	Entity	Lease	Well Type	Status
RWS 5ML-9-9-24	RWS 5ML-9-9-24	SWNW	09	090S	240E	4304738645		Federal	GW	APD
RWS 12ML-9-9-24	RWS 12ML-9-9-24	NWSW	09	090S	240E	4304738646		Federal	GW	APD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER _____

2. NAME OF OPERATOR:
QUESTAR EXPLORATION AND PRODUCTION COMPANY

3. ADDRESS OF OPERATOR: 1050 17th Street Suite 500 CITY Denver STATE CO ZIP 80265 PHONE NUMBER: (303) 308-3068

4. LOCATION OF WELL

FOOTAGES AT SURFACE: attached

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
see attached

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
see attached

7. UNIT or CA AGREEMENT NAME:
see attached

8. WELL NAME and NUMBER:
see attached

9. API NUMBER:
attached

10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 1/1/2007	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Operator Name Change
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective January 1, 2007 operator of record, QEP Uinta Basin, Inc., will hereafter be known as QUESTAR EXPLORATION AND PRODUCTION COMPANY. This name change involves only an internal corporate name change and no third party change of operator is involved. The same employees will continue to be responsible for operations of the properties described on the attached list. All operations will continue to be covered by bond numbers:

Federal Bond Number: 965002976 (BLM Reference No. ESB000024)

Utah State Bond Number: 965003033

Fee Land Bond Number: 965003033

Current operator of record, QEP UINTA BASIN, INC., hereby resigns as operator of the properties as described on the attached list.

Jay B. Neese, Executive Vice President, QEP Uinta Basin, Inc.

Successor operator of record, QUESTAR EXPLORATION AND PRODUCTION COMPANY, hereby assumes all rights, duties and obligations as operator of the properties as described on the attached list

Jay B. Neese, Executive Vice President
Questar Exploration and Production Company

NAME (PLEASE PRINT) Debra K. Stanberry

TITLE Supervisor, Regulatory Affairs

SIGNATURE

DATE 3/16/2007

(This space for State use only)

RECEIVED

APR 19 2007

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: see attached
2. NAME OF OPERATOR: QUESTAR EXPLORATION AND PRODUCTION COMPANY	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: see attached
3. ADDRESS OF OPERATOR 1050 17th Street Suite 500 Denver STATE CO ZIP 80265	7. UNIT or CA AGREEMENT NAME: see attached
4. LOCATION OF WELL FOOTAGES AT SURFACE: attached	8. WELL NAME and NUMBER: see attached
PHONE NUMBER: (303) 308-3068	9. API NUMBER: attached
	10. FIELD AND POOL, OR WILDCAT:

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 1/1/2007	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Well Name Changes
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

PER THE ATTACHED LIST OF WELLS, QUESTAR EXPLORATION AND PRODUCTION COMPANY REQUESTS THAT THE INDIVIDUAL WELL NAMES BE UPDATED IN YOUR RECORDS.

NAME (PLEASE PRINT) Debra K. Stanberry

TITLE Supervisor, Regulatory Affairs

SIGNATURE

DATE 4/17/2007

(This space for State use only)

RECEIVED

APR 19 2007

DIV. OF OIL, GAS & MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

April 23, 2007

Questar Exploration and Production Company
1050 17th Street, Suite 500
Denver, Colorado 80265

Re: Big Valley Unit
Uintah County, Utah

Gentlemen:

On April 12, 2007, we received an indenture dated April 6, 2007, whereby QEP Uinta Basin, Inc. resigned as Unit Operator and Questar Exploration and Production Company was designated as Successor Unit Operator for the Big Valley Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective April 23, 2007. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Big Valley Unit Agreement.

Your nationwide oil and gas bond No. ESB000024 will be used to cover all federal operations within the Big Valley Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Greg J. Noble

Greg J. Noble
Acting Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
File - Big Valley Unit (w/enclosure)
Agr. Sec. Chron
Reading File
Central Files

UT922:TAThompson:tt:4/23/07

RECEIVED

APR 30 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires July 31, 1996

5. Lease Serial No.

UTU-73456

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA/Agreement, Name and/or No.

BIG VALLEY UNII # UTU-81308X

8. Well Name and No.

RWS 12ML-6-9-24

9. API Well No.

43-047-37312

10. Field and Pool, or Exploratory Area

UNDESIGNATED

11. County or Parish, State

UINTAH

SUBMIT IN TRIPLICATE - Original instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

QEP Uinta Basin, Inc.

Contact: Darryl Knop

3a. Address

11002 East 17500 South, Vernal, UT 84078

3b. Phone No. (include area code)

435-828-0394

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

2180' FSL 698' FWL NWSW, LOT 6, SECTION 6, T9S, R24E

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input checked="" type="checkbox"/> Alter Casing (SURFACE)	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once Testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

QEP Uinta Basin, Inc., proposes to change surface casing from what was originally approved from 450' to 2250'. Surface casing will be set 300' below birds nest. Surface casing will be 9 5/8" J-55, 36 lbs., cement to surface with premium cement.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Jan Nelson

Signature

Title

Regulatory Affairs

Date

January 2, 2007

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

RECEIVED

JAN 05 2007

State of Utah
Division of Oil, Gas and Mining

ENTITY ACTION FORM - FORM 6

OPERATOR: QEP Uinta Basin, Inc.
ADDRESS: 11002 East 17500 South
Vernal, Utah 84078-8526

OPERATOR ACCT. No. N-2460

(435)781-4300

Action Code	Current Entity No.	New Entity No.	API Number	Well Name	QQ	SC	TP	RG	County	Spud Date	Effective Date
A	99999	15947	43-047-37312	RWS 12ML 6 9 24	NWSW	6	9S	24E	Uintah	1/24/07	2/22/07

WELL 1 COMMENTS:

W5MVD

CONFIDENTIAL

WELL 2 COMMENTS:

WELL 3 COMMENTS:

WELL 4 COMMENTS:


WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected

(3/89)


Signature

Office Administrator II
Title

2/1/07
Date

Phone No. (435)781-4342

CONFIDENTIAL

RECEIVED

FEB 20 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

CONFIDENTIAL

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir
Use "APPLICATION FOR PERMIT--" for such proposals

SUBMIT IN TRIPLICATE - Amended Report on 1/15/07

1. Type of Well

Oil

Gas

☐

Well

☒

Well

☐

Other

2. Name of Operator

QEP, UINTA BASIN, INC.

Contact: dahn.caldwell@questar.com

3. Address and Telephone No.

1571 EAST 1700 SOUTH - VERNAL, UT 84078

435-781-4342 Fax 435-781-4357

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

2180' FSL, 698' FWL, NWSW, SEC 6-T9S-R24E

5. Lease Designation and Serial No.

UTU-73456

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

BIG VALLEY UNIT
UTU-81308X

8. Well Name and No.

RWS 12ML 6 9 24

9. API Well No.

43-047-37312

10. Field and Pool, or Exploratory Area

NATURAL BUTTES

11. County or Parish, State

UINTAH

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐

Notice of Intent

☒

Subsequent Report

☐

Final Abandonment Notice

TYPE OF ACTION

☐

Abandonment

☐

Recompletion

☐

Plugging Back

☐

Casing Repair

☐

Altering Casing

☒

Other SPUD

☐

Change of Plans

☐

New Construction

☐

Non-Routine Fracturing

☐

Water Shut-Off

☐

Conversion to Injection

☐

Dispose Water

(Note) Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

On 1/24/07 - Drilled 40' of 20" conductor hole. Set 40' of 14" conductor pipe. Cmted w/ Ready Mix.

On 1/27/07 - Drilled 12-1/4" hole to 2282'KB. Ran 51 jts of 9-5/8", 36#, J-55 csg to 2244'KB. Cmted surface csg w/ 200 sxs of Class 'G' cmt and 635 sxs for Top Offs.

RECEIVED

FEB 20 2007

DIV. OF OIL, GAS & MINING

3 - BLM, 2- Utah OG&M, 1 - Denver, 1 - file Word file server

14. I hereby certify that the foregoing is true and correct.
Signed **Dahn F. Caldwell**

Office Administrator II

Date 2/1/07

(This space for Federal or State office use)

Approved by:

Title

Date

Conditions of approval, if any

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CONFIDENTIAL

CONFIDENTIAL

Questar E & P					Page 1 of 2
Operations Summary Report					
Well Name: RWS 12ML-6-9-24			Spud Date: 2/12/2007		
Location: 6- 9-S 24-E 26			Rig Release: 2/18/2007		
Rig Name: TRUE			Rig Number: 26		
43-047-37312					
Date	From - To	Hours	Code	Sub Code	Description of Operations
1/29/2007	-		LOC	2	MIRU PETE MARTIN 1/24/2007. DRILL 40' OF 20" CONDUCTOR HOLE. CEMENT 40' OF 14" CONDUCTOR PIPE WITH READY MIX. DRILL RAT AND MOUSE HOLES FOR TRUE RIG NO. 26 RIG DOWN AND RELEASE 1/24/2007
	-		DRL	8	MIRU BILL JR. RATHOLE DRILLING ON 1/27/2007. DRILLED 2282' KBM OF 12 1/4" HOLE. RUN 51 JOINTS OF 9 5/8" 36 POUND J-55 TO DEPTH OF 2243.7' KBM. RIG DOWN AND RELEASE ON 1/28/2007
	-		CMT	2	(HIT WATER AT 1560 AND 1890) MIRU BIG 4 CEMENTERS ON 1/28/2007. CEMENT SURFACE CASING WITH 200 SACKS OF LEAD AND 635 SACKS FOR TOP OFFS. RIG DOWN AND RELEASE 1/29/2007
2/11/2007	06:00 - 06:00	24.00	LOC	3	MOVE RIG FROM RWS 2ML-5-9-24 RELEASED WESROC TRUCKS AT 1700 HRS.
2/12/2007	06:00 - 07:00	1.00	LOC	4	FINNISH RIG UP
	07:00 - 10:00	3.00	BOP	1	NIPPLE UP 3000 BOP
	10:00 - 14:00	4.00	BOP	2	RIG UP SINGLE JACK TESTERS PRESSURE TEST PIPE, BLIND RAMS, CHOKE LINE-MANIFOLD, KILL LINE, UPPER-LOWER KELLY, SAFETY VALVES TO 3000-PSI. TEST ANNULAR TO 1500-PSI. TEST CASING TO 1500-PSI. FUNCTION AND CHECK ACCUMULATOR.
	14:00 - 15:30	1.50	TRP	1	P/U BHA (HC504ZX. HUNTING .22 MM. 2 IBS'. 15 DRILL COLLARS.)
	15:30 - 17:00	1.50	TRP	2	P/U DRILL PIPE TO 2089'
	17:00 - 18:30	1.50	DRL	4	DRILL CEMENT AND EQUIPMENT. (FLOAT AT 2196 SHOE AT 2242)
	18:30 - 19:30	1.00	DRL	1	DRILL F/2243-2344
	19:30 - 20:00	0.50	SUR	1	SURVEY AT 2269 1 DEGREE
	20:00 - 20:30	0.50	DRL	1	DRILL F/2344-2375
	20:30 - 21:00	0.50	RIG	1	RIG SERVICE
	21:00 - 03:00	6.00	DRL	1	DRILL F/2375-3101
	03:00 - 03:30	0.50	SUR	1	SURVEY AT 3020 1 DEGREE
	03:30 - 06:00	2.50	DRL	1	DRILL F/3101-3400
2/13/2007	06:00 - 09:00	3.00	DRL	1	DRILL F/ 3400' T/ 3798'
	09:00 - 09:30	0.50	SUR	1	SURVEY @ 3721' 1 DEG.
	09:30 - 11:30	2.00	DRL	1	DRILL F/ 3798' T/ 4083'
	11:30 - 12:00	0.50	RIG	1	RIG SERVICE.
	12:00 - 01:30	13.50	DRL	1	DRILL F/ 4083' T/ 4809'
	01:30 - 02:00	0.50	SUR	1	SURVEY @ 4720' 1 1/2 DEG
	02:00 - 03:00	1.00	DRL	1	DRILL F/ 4809' T/ 4865'
	03:00 - 04:30	1.50	WCL	1	WELL KICKING. P/U CLOSE IN SICP 300# CIRC & MUD UP.
	04:30 - 06:00	1.50	DRL	1	DRILL F/ 4865' T/ 4920' (MUD WT 8.9 VIS 38)
2/14/2007	06:00 - 09:00	3.00	DRL	1	DRILL F/ 4920' T/ 5032'
	09:00 - 12:00	3.00	TRP	10	TRIP F/ BIT #2 (L/D STAB)
	12:00 - 12:30	0.50	RIG	1	RIG SERVICE.
	12:30 - 14:30	2.00	TRP	10	TRIP IN HOLE.
	14:30 - 15:00	0.50	REAM	1	WASH 60' BTM.
	15:00 - 23:30	8.50	DRL	1	DRILL F/ 5032' T/ 5875'
	23:30 - 00:00	0.50	SUR	1	SURVEY @ 5800' 4 3/4 DEG.
	00:00 - 06:00	6.00	DRL	1	DRILL F/ 5875' T/ 6410' (MUD WT 9.7 VIS 40)
2/15/2007	06:00 - 06:30	0.50	SUR	1	SURVEY @ 6340' 6 DEG
	06:30 - 07:00	0.50	DRL	1	DRILL F/ 6410' T/ 6446'
	07:00 - 13:00	6.00	TRP	2	TRIP P/U (1) STAB
	13:00 - 13:30	0.50	REAM	1	WASH 50' BTM.
	13:30 - 17:00	3.50	DRL	1	DRILL F/ 6446' T/ 6736'
	17:00 - 17:30	0.50	SUR	1	SURVEY @ 6663' 6 DEG

Printed: 3/6/2007 12:55:48 PM

RECEIVED

MAR 06 2007

DIV. OF OIL, GAS & MINING

Questar E & P
Operations Summary Report

Page 2 of 2

Well Name: RWS 12ML-6-9-24
Location: 6-9-S 24-E 26
Rig Name: TRUE

Spud Date: 2/12/2007
Rig Release: 2/18/2007
Rig Number: 26

Date	From - To	Hours	Code	Sub Code	Description of Operations
2/15/2007	17:30 - 21:30	4.00	DRL	1	DRILL F/ 6736' T/ 7051'
	21:30 - 22:00	0.50	SUR	1	SURVEY @ 6976' 4 3/4 DEG.
	22:00 - 06:00	8.00	DRL	1	DRILL F/ 7051' T/ 7415'
2/16/2007	06:00 - 09:00	3.00	DRL	1	DRILL F/ 415' T/ 7472
	09:00 - 09:30	0.50	SUR	1	PUMP PILL. DROP SURVEY.
	09:30 - 13:00	3.50	TRP	10	TRIP F/ BIT #3 (P/U .16 MOTOR)
	13:00 - 13:30	0.50	RIG	1	RIG SERVICE.
	13:30 - 16:30	3.00	TRP	10	TRIP IN HOLE.
	16:30 - 17:00	0.50	REAM	1	WASH 60' BTM.
	17:00 - 06:00	13.00	DRL	1	DRILL F/ 7472' T/ 8060'
2/17/2007	06:00 - 10:30	4.50	DRL	1	DRILL F/ 8060' T/ 8250'
	10:30 - 11:30	1.00	TRP	14	SHORT TRIP 10 STD.
	11:30 - 15:30	4.00	DRL	1	DRILL F/ 8250' T/ 8325' (ORDER F/ STEVE HALL TO DRILL T/ 8325') (T.D @ 15:30 2/16/2007)
	15:30 - 16:30	1.00	CIRC	1	CIRC BTM UP.
	16:30 - 17:00	0.50	SUR	1	SURVEY. PUMP PILL. @ 8265 5 1/2 DEG
	17:00 - 21:30	4.50	TRP	2	TRIP OUT F/ LOGS. (SLM 8327.90')
	21:30 - 22:00	0.50	LOG	1	R/U LOGGING TOOLS (SAFTY MEETING)
	22:00 - 01:30	3.50	LOG	1	LOGGING (LOG DEPTH 8327')
	01:30 - 02:30	1.00	LOG	1	L/D LOGGING TOOLS.
	02:30 - 03:30	1.00	TRP	2	TRIP IN HOLE
2/18/2007	03:30 - 04:30	1.00	RIG	6	CUT DRILL LINE
	04:30 - 06:00	1.50	TRP	2	TRIP IN HOLE.
	06:00 - 07:00	1.00	TRP	2	TRIP IN HOLE.
	07:00 - 08:00	1.00	CIRC	1	CIRC BTM UP. PUMP PILL. R/U CSG CREW. (SAFTY MEETING)
	08:00 - 15:00	7.00	TRP	3	L/D DRILL STRING.
	15:00 - 16:00	1.00	CSG	1	R/U CSG CREW. (SAFTY MEETING)
	16:00 - 20:30	4.50	CSG	2	RUN 188 JTS 4 1/2" 11.60# M-80.CSG. TOTAL 8325'
	20:30 - 21:00	0.50	CMT	1	R/U CMT HEAD.
	21:00 - 22:00	1.00	CIRC	1	CIRC BTM UP. R/D CSG CREW. (SAFTY WITH HALLIBURTON)
	22:00 - 01:00	3.00	CMT	2	CMT W/ 400 SKS LEAD. 1060 SKS TAIL. DISP W/ 128 BBL 2% KCL.
2/19/2007	01:00 - 01:30	0.50	CMT	1	R/D CEMENTERS
	01:30 - 03:00	1.50	BOP	1	N/D BOP. SET SLIPS W/ 90,000
	03:00 - 06:00	3.00	LOC	7	CLEAN PITS
	06:00 - 07:00	1.00	LOC	7	CLEAN PITS RIG RELEASE
	07:00 - 18:00	11.00	LOC	4	R.D.R.T.

Printed: 3/6/2007 12:55:48 PM

Questar E & P
Operations Summary Report

Page 1 of 4

Well Name: RWS 12ML-6-9-24
Location: 6- 9-S 24-E 26
Rig Name:

Spud Date: 2/12/2007
Rig Release:
Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
2/22/2007	06:00 - 16:00	10.00	BOP	1	On 2/21/07 MIRU Rocky Mtn Well Service to start completion of well. ND WH & NU BOP's. SIFN. 24 Hr Forecast: Will tally & rabbit in the hole w/ bit & scraper & tbq. Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279' On 2/22/07 tally & rabbit in the hole w/ a 3-7/8" bit & 4-1/2" csg scraper & new 2-3/8" EUE 8rd 4.7# J-55 tbq to tag at 8207'. Circ hole clean with 2% KCL water. Pull bit to 3800'. SIFN. On 2/23/07 finish POOH w/ bit & scraper & tbq. ND BOP's & NU 4-1/16" 10M# frac valve. MIRU Cutters WL and ran a CBL/VDL/GR log from tag @ 8211' to 35' with top of cement est at 350'. Pressure test csg & frac valve to 5000# and held OK. Correlated bond log to Halliburton Density log dated 2/17/07. Perforated the following Lower Mesa Verde intervals per the CBL log dated 2/23/07 at 4 JPF and 90° phasing using a 3-1/8" csg gun and "PowerPak" charges: 7464' - 7468'; 7514' - 7518' & 7548' - 7552' (48 holes). RDMO Cutters WL. Breakdown the perfs at 2900# and pump 10 bbls of 2% KCL water at 1.6 BPM at 2600# & ISIP = 2400#. Bled off the well and diesel the wellhead and SIFW. 24 Hr Forecast: Will frac the above interval and continue with additional zones. Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279' Perfs Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552'
2/26/2007	06:00 - 16:00	10.00	PERF	2	
2/27/2007	06:00 - 16:00	10.00	STIM	3	On 2/26/07 SICP = 1240#. MIRU Halliburton frac crew & Cutters WL. Zone #1 - Lower Mesa Verde perforated interval 7454' - 7468'; 7514' - 7518' & 7548' - 7552'. Frac gross interval LMV interval 7464' - 7552' down 4-1/2" csg using a slick water 2% KCL water system as follows: Pump 400 gals of 28% HCL acid and frac with a 20070 gal pad and stage 0.25 ppg to 2 ppg 20/40 mesh sand in 64000 gals of fluid and flush with 400 gals of 28% HCL acid and 2507 gals of slick water. Screened out with 1.55 ppg sand in formation leaving est. 2500# of sand in the csg. Total sand in formation is 48500# and a total load of 2095 bbls. Max rate = 53.5 BPM & avg rate = 51.8 BPM, max psi = 6877#, avg psi = 4437#, (1.34 FG). Lubricate in a 4-1/2" comp frac plug and set @ 6100'. Zone #2 - Perforate Wasatch intervals 5946' - 5956' & 6042' - 6048' per the CBL log dated 2/23/07 @ 3 JPF using a 3-1/8" csg gun and "Power Pak" charges (48 holes). Frac gross perforated Wasatch interval 5946' - 6048' down csg using a 13 vix 2% KCL x-linked gel water system as follows: Pump @ 4000 gal pad & stage 1-5 ppg 20/40 mesh sand in 13100 gals of fluid & flush with 400 gals of 28% HCL acid and 3460 gals of slick water. Total of 49500# of 20/40 sand and a total load of 517 bbls. Max rate = 40.8 BPM, avg rate = 35 BPM, max psi = 5074#, avg psi = 3053#, ISIP = 2550# (.88). Lubricate in a 4-1/2" comp frac plug & set @ 5400'. Zone #3 - Perforate per the above log Wasatch intervals 5331' - 5335', 5356' - 5362' & 5366' - 5372' using a 3-1/8" csg gun at 3 JPF with 120° phasing & "Prospector" charges. Frac gross Wasatch perforated interval 5331' - 5372' down csg using a 13 vis. 2% KCL x-linked gel water system as follows: Pump a 6600 gal pad and stage 1-5 ppg 20/40 mesh sand in 21000 gals of fluid and flush w/ 600 gals

Printed: 3/6/2007 12:56:45 PM

Operations Summary Report

Well Name: RWS 12ML-6-9-24
 Location: 6- 9-S 24-E 26
 Rig Name:

Spud Date: 2/12/2007
 Rig Release:
 Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
2/27/2007	06:00 - 16:00	10.00	STIM	3	<p>of 28% HCL acid and 2904 gals of slick water. Total of 79300# of 20/40 mesh sand and a total load of 855 bbls. Max rate = 48.7 BPM, avg rate = 41.1 BPM, max psi = 3124#, avg psi = 2677#, ISIP = 1950#. (.80). Lubricate in a comp frac plug & set at 5150'.</p> <p>Zone #4 - Perforate per the above log and gun at 3 JPF Wasatch intervals 4815' - 4819', 4884' - 4888' & 5072' - 5080' (48 holes). Frac gross perforated Wasatch interval 4815' - 5080' down csg using a 13 vis. 2% KCL x-linked gel water system as follows: Pump a 8700 gal pad and stage 1-5 ppg 20/40 mesh sand in 23000 gals of fluid and flush with 3087 gals of slick water. Total of 100,480# of 20/40 sand and a total load of 914 bbls. Max rate = 53.9 BPM, avg rate = 50.9 BPM, max psi = 3717#, avg psi = 3463#, ISIP = 2380# (.92). SI the well and RDMO Halliburton frac crew. After a 3 hour SI period SICP = 660#. Open the csg on various chokes overnight and at 5:00 AM on 2/27/07 after an 11 hour flow period. FCP = 500# on 1 18/64" choke at 40 BPH w/ lt. sand & a total est recovered 390 bbls. SI the well at 5:00 AM.</p> <p>24 Hr Forecast: Set a top kill plug this AM.</p> <p>Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'</p>
2/28/2007	06:00 - 16:00	10.00	CIRC	1	<p>On AM of 2/27/07 SICP = 550#. RU Cutters WL & set a 4-1/2" CBP @ 4600'. RDMO Cutters WL. Bled off csg. ND frac valve & NU BOP's. RIH w/ a 3-3/8" & pump off bit sub assembly and tbg and tag CBP @ 4800' and drill out plug. Took a 200# flow on a 48/64" choke. Continue in the hole & drill out frac plugs at 5150'; 5400' & 6100' with a 150-200# flow on a 48/64" choke. Continue in the hole and tag sand at 7840'. Circ hole clean @ 7640' w/ 2% KCL water. Pull bit to 7420' & SIFN.</p> <p>24 Hr Forecast: Will clean out to PBTD & land tbg & attempt to clean up well to the pit.</p> <p>Csg Size: 4-1/2" 11.6# M-80</p>

Operations Summary Report

Well Name: RWS 12ML-6-9-24
 Location: 6- 9-S 24-E 26
 Rig Name:

Spud Date: 2/12/2007
 Rig Release:
 Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
2/28/2007	06:00 - 16:00	10.00	CIRC	1	<p>Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'</p>
3/1/2007	06:00 - 16:00	10.00	CIRC	1	<p>On AM of 2/28/07 SITP = 0# w/ float in string & SICP = 400#. Continue in the hole with bit & tbg and tag fill @ 7630'. Clean out sand to PBTD of 8211'. Circ hole clean w/ 2% KCL water. Pull bit to 7390' & land the tbg in the hanger. ND BOP's and NU WH. Drop ball and shear off bit sub assembly. Open the tbg to the pit on a 48/64" choke with FTP = 50# & SICP = 700#. Continue to flow the tbg to the pit on various chokes overnight and at 5:00 AM on 3/1/07 FTP = 1250# on a 28/64" choke with SICP = 1850# and flowing gas cut water at a rate of 25 BPH and light sand. Recovered an est 485 bbls in the last 16 hours. Will continue to clean up well and should go to production department early PM.</p> <p>Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819'</p>

Questar E & P
Operations Summary Report

Page 4 of 4

Well Name: RWS 12ML-6-9-24
Location: 6- 9-S 24-E 26
Rig Name:

Spud Date: 2/12/2007
Rig Release:
Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
3/1/2007	06:00 - 16:00	10.00	CIRC	1	4884' - 4888' 5072' - 5080'
3/2/2007	06:00 - 16:00	10.00	LOC	4	On 7:00 AM on 3/1/07 FTP=1250# on a 28/64" choke with SICP=1860# and an est.rate of 15 bbl.per hour of gas cut water to the pit. SI the well and hook up to production facilities. Too windy to rig down. Turn well over to production department. On 3/2/07 will RDMO Rocky Mtn.Well Service. Final report of well completion. Will update tbq. detail. Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279' Load from yesterday: 3450 Minus daily recovery 50 LLTR: 3400 Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'

Printed: 3/6/2007 12:56:45 PM

CONFIDENTIAL

Questar E & P						Page 1 of 5
Operations Summary Report						
Well Name: RWS 12ML-6-9-24				Spud Date: 2/12/2007		
Location: 6- 9-S 24-E 26				Rig Release:		
Rig Name:				Rig Number:		
43-047-37312						
Date	From - To	Hours	Code	Sub Code	Description of Operations	
2/22/2007	06:00 - 16:00	10.00	BOP	1	<p>On 2/21/07 MIRU Rocky Mtn Well Service to start completion of well. ND WH & NU BOP's. SIFN.</p> <p>24 Hr Forecast: Will tally & rabbit in the hole w/ bit & scraper & tbq.</p> <p>Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279'</p>	
2/26/2007	06:00 - 16:00	10.00	PERF	2	<p>On 2/22/07 tally & rabbit in the hole w/ a 3-7/8" bit & 4-1/2" csg scraper & new 2-3/8" EUE 8rd 4.7# J-55 tbq to tag at 8207'. Circ hole clean with 2% KCL water. Pull bit to 3800'. SIFN.</p> <p>On 2/23/07 finish POOH w/ bit & scraper & tbq. ND BOP's & NU 4-1/16" 10M# frac valve. MIRU Cutters WL and ran a CBL/VDL/GR log from tag @ 8211' to 35' with top of cement est at 350'. Pressure test csg & frac valve to 5000# and held OK. Correlated bond log to Halliburton Density log dated 2/17/07. Perforated the following Lower Mesa Verde intervals per the CBL log dated 2/23/07 at 4 JPF and 90° phasing using a 3-1/8" csg gun and "PowerPak" charges: 7464' - 7468'; 7514' - 7518' & 7548' - 7552' (48 holes). RDMO Cutters WL. Breakdown the perfs at 2900# and pump 10 bbls of 2% KCL water at 1.6 BPM at 2600# & ISIP = 2400#. Bled off the well and diesel the wellhead and SIFW.</p> <p>24 Hr Forecast: Will frac the above interval and continue with additional zones.</p> <p>Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552'</p>	
2/27/2007	06:00 - 16:00	10.00	STIM	3	<p>On 2/26/07 SICIP = 1240#. MIRU Halliburton frac crew & Cutters WL.</p> <p>Zone #1 - Lower Mesa Verde perforated interval 7454' - 7468'; 7514' - 7518' & 7548' - 7552'. Frac gross interval LMV interval 7464' - 7552' down 4-1/2" csg using a slick water 2% KCL water system as follows: Pump 400 gals of 28% HCL acid and frac with a 20070 gal pad and stage 0.25 ppg to 2 ppg 20/40 mesh sand in 64000 gals of fluid and flush with 400 gals of 28% HCL acid and 2507 gals of slick water. Screened out with 1.55 ppg sand in formation leaving est. 2500# of sand in the csg. Total sand in formation is 48500# and a total load of 2095 bbls. Max rate = 53.5 BPM & avg rate = 51.8 BPM, max psi = 6877#, avg psi = 4437#, (1.34 FG). Lubricate in a 4-1/2" comp frac plug and set @ 6100'.</p> <p>Zone #2 - Perforate Wasatch intervals 5946' - 5956' & 6042' - 6048' per the CBL log dated 2/23/07 @ 3 JPF using a 3-1/8" csg gun & "Power Pak" charges (48 holes). Frac gross perforated Wasatch interval 5946' - 6048' down csg using a 13 vix 2% KCL x-linked gel water system as follows: Pump @ 4000 gal pad & stage 1-5 ppg 20/40 mesh sand in 13100 gals of fluid & flush with 400 gals of 28% HCL acid and 3460 gals of slick water. Total of 49500# of 20/40 sand and a total load of 517 bbls. Max rate = 40.8 BPM, avg rate = 35 BPM, max psi = 5074#, avg psi = 3053#, ISIP = 2550# (.88). Lubricate in a 4-1/2" comp frac plug & set @ 5400'.</p> <p>Zone #3 - Perforate per the above log Wasatch intervals 5331' - 5335', 5356' - 5362' & 5366' - 5372' using a 3-1/8" csg gun at 3 JPF with 120° phasing & "Prospector" charges. Frac gross Wasatch perforated interval 5331' - 5372' down csg using a 13 vis. 2% KCL x-linked gel water system as follows: Pump a 6600 gal pad and stage 1-5 ppg 20/40 mesh sand in 21000 gals of fluid and flush w/ 600 gals</p>	

Printed: 4/5/2007 9:53:08 AM

RECEIVED

APR 05 2007

DIV. OF OIL, GAS & MINING

Questar E & P
Operations Summary Report

Page 2 of 5

Well Name: RWS 12ML-6-9-24
Location: 6- 9-S 24-E 26
Rig Name:

Spud Date: 2/12/2007
Rig Release:
Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
2/27/2007	06:00 - 16:00	10.00	STIM	3	<p>of 28% HCL acid and 2904 gals of slick water. Total of 79300# of 20/40 mesh sand and a total load of 855 bbls. Max rate = 48.7 BPM, avg rate = 41.1 BPM, max psi = 3124#, avg psi = 2677#, ISIP = 1950#. (.80). Lubricate in a comp frac plug & set at 5150'.</p> <p>Zone #4 - Perforate per the above log and gun at 3 JPF Wasatch intervals 4815' - 4819', 4884' - 4888' & 5072' - 5080' (48 holes). Frac gross perforated Wasatch interval 4815' - 5080' down csg using a 13 vis. 2% KCL x-linked gel water system as follows: Pump a 8700 gal pad and stage 1-5 ppg 20/40 mesh sand in 23000 gals of fluid and flush with 3087 gals of slick water. Total of 100,480# of 20/40 sand and a total load of 914 bbls. Max rate = 53.9 BPM, avg rate = 50.9 BPM, max psi = 3717#, avg psi = 3463#, ISIP = 2380# (.92). SI the well and RDMO Halliburton frac crew. After a 3 hour SI period SICP = 660#. Open the csg on various chokes overnight and at 5:00 AM on 2/27/07 after an 11 hour flow period. FCP = 500# on 1 18/64" choke at 40 BPH w/ lt. sand & a total est recovered 390 bbls. SI the well at 5:00 AM.</p> <p>24 Hr Forecast: Set a top kill plug this AM.</p> <p>Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'</p>
2/28/2007	06:00 - 16:00	10.00	CIRC	1	<p>On AM of 2/27/07 SICP = 550#. RU Cutters WL & set a 4-1/2" CBP @ 4600'. RDMO Cutters WL. Bled off csg. ND frac valve & NU BOP's. RIH w/ a 3-3/8" & pump off bit sub assembly and tbg and tag CBP @ 4800' and drill out plug. Took a 200# flow on a 48/64" choke. Continue in the hole & drill out frac plugs at 5150'; 5400' & 6100' with a 150-200# flow on a 48/64" choke. Continue in the hole and tag sand at 7840'. Circ hole clean @ 7640' w/ 2% KCL water. Pull bit to 7420' & SIFN.</p> <p>24 Hr Forecast: Will clean out to PBTD & land tbg & attempt to clean up well to the pit.</p> <p>Csg Size: 4-1/2" 11.6# M-80</p>

Printed: 4/5/2007 9:53:08 AM

Questar E & P
Operations Summary Report

Page 3 of 5

Well Name: RWS 12ML-6-9-24
Location: 6- 9-S 24-E 26
Rig Name:

Spud Date: 2/12/2007
Rig Release:
Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
2/28/2007	06:00 - 16:00	10.00	CIRC	1	<p>Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'</p>
3/1/2007	06:00 - 16:00	10.00	CIRC	1	<p>On AM of 2/28/07 SITP = 0# w/ float in string & SICP = 400#. Continue in the hole with bit & tbq and tag fill @ 7630'. Clean out sand to PBTD of 8211'. Circ hole clean w/ 2% KCL water. Pull bit to 7390' & land the tbq in the hanger. ND BOP's and NU WH. Drop ball and shear off bit sub assembly. Open the tbq to the pit on a 48/64" choke with FTP = 50# & SICP = 700#. Continue to flow the tbq to the pit on various chokes overnight and at 5:00 AM on 3/1/07 FTP = 1250# on a 28/64" choke with SICP = 1850# and flowing gas cut water at a rate of 25 BPH and light sand. Recovered an est 485 bbbls in the last 16 hours. Will continue to clean up well and should go to production department early PM.</p> <p>Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279'</p> <p>Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819'</p>

Printed: 4/5/2007 9:53:08 AM

Questar E & P
Operations Summary Report

Page 4 of 5

Well Name: RWS 12ML-6-9-24
Location: 6- 9-S 24-E 26
Rig Name:

Spud Date: 2/12/2007
Rig Release:
Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
3/1/2007	06:00 - 16:00	10.00	CIRC	1	4884' - 4888' 5072' - 5080'
3/2/2007	06:00 - 16:00	10.00	LOC	4	On 7:00 AM on 3/1/07 FTP=1250# on a 28/64" choke with SICP=1860# and an est.rate of 15 bbl.per hour of gas cut water to the pit. SI the well and hook up to production facilities. Too windy to rig down. Turn well over to production department. On 3/2/07 will RDMO Rocky Mtn.Well Service. Final report of well completion. Will update tbq. detail. Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279' Load from yesterday: 3450 Minus daily recovery 50 LLTR: 3400 Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'
3/30/2007	06:00 - 16:00	10.00	OTH		Update on tbq detail only for final report of well. KB 12.0 Hanger 0.85 230 Jts of 2-3/8" 4.7# EUE 8rd J-55 Tbg 7343.56 1.81" "F" Nipple .91 1 Jt Tbg 31.67 Shear Sub .91 Tbg Tail @ 7389.90 "F" Nipple @ 7357.32 Csg Size: 4-1/2" 11.6# M-80 Csg Depth: 8325', FC @ 8279' Load from yesterday: 3450 Minus daily recovery 50 LLTR: 3400

Printed: 4/5/2007 9:53:08 AM

Operations Summary Report

Well Name: RWS 12ML-6-9-24
Location: 6- 9-S 24-E 26
Rig Name:

Spud Date: 2/12/2007
Rig Release:
Rig Number:

Date	From - To	Hours	Code	Sub Code	Description of Operations
3/30/2007	06:00 - 16:00	10.00	OTH		Perfs Zone #1 Lower Mesa Verde 7484' - 7488' 7514' - 7518' 7548' - 7552' Zone #2 Wasatch 5946' - 5956' 6042' - 6048' Zone #3 Wasatch 5331' - 5335' 5356' - 5362' 5366' - 5372' Zone #4 Wasatch 4815' - 4819' 4884' - 4888' 5072' - 5080'

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side).

Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

CONFIDENTIAL


WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> Other _____		7. UNIT AGREEMENT NAME BIG VALLEY UTU-81308X	
b. TYPE OF COMPLETION NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR <input type="checkbox"/> Other _____		8. FARM OR LEASE NAME N/A	
2. NAME OF OPERATOR QUESTAR EXPLORATION & PRODUCTION CO.		9. WELL NO. RWS 12ML 6 9 24	
3. ADDRESS OF OPERATOR 1571 East 1700 South - Vernal, UT 84078		10. FIELD AND POOL, OR WILDCAT UNDESIGNATED	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)* At surface NWSW, 2180' FSL, 698' FWL, SEC 6-T9S-R24E At top rod, interval reported below NWSW, 2180' FSL, 698' FWL, SEC 6-T9S-R24E At total depth NWSW, 2180' FSL, 698' FWL, SEC 6-T9S-R24E		11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA SEC 6-T9S-R24E	
14. PERMIT NO. 43-047- 37312		12. COUNTY OR PARISH UINTAH	
DATE ISSUED		13. STATE UT	
15. DATE SPURRED 01/24/07	16. DATE T.D. REACHED 02/16/07	17. DATE COMPL. (Ready to prod.) 03/01/07	18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* KB
20. TOTAL DEPTH, MD & TVD 8,325'	21. PLUG BACK T.D., MD & TVD 8,211'	22. IF MULTIPLE COMPL., HOW MANY*	23. INTERVALS DRILLED BY ROTARY TOOLS CABLE TOOLS
24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)* SEE ATTACHMENT PAGE 1			25. WAS DIRECTIONAL SURVEY MADE NO
26. TYPE ELECTRIC AND OTHER LOGS RUN GR/CBL, HRI & SPECTRAL DENSITY DSN			27. WAS WELL CORED NO
28. CASING RECORD (Report all strings set in well)			
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE
9-5/8"	36#	2,244'	12-1/4"
4-1/2"	11.6#	8,325'	4-1/2"
29. LINER RECORD			
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*
30. TUBING RECORD			
SIZE	DEPTH SET (MD)	PACKER SET (MD)	
2-3/8"	7,390'		
31. PERFORATION RECORD (Interval, size and number) SEE ATTACHMENT PAGE 1			
32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
DEPTH INTERVAL (MD)		AMOUNT AND KIND OF MATERIAL USED	
SEE ATTACHMENT PG 1		SEE ATTACHMENT PAGE 1	
33.* PRODUCTION			
DATE FIRST PRODUCTION 03/01/07		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) FLOWING	
WELL STATUS (Producing or shut-in) PRODUCING			
DATE OF TEST 03/03/07	HOURS TESTED 24	CHOKE SIZE 16/64"	PROD'N FOR TEST PERIOD 10
OIL--BBL.	GAS--MCF.	WATER--BBL.	GAS-OIL RATIO
1,408	1,408	236	
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL GRAVITY-API (CORR.)
1,408	1,960		
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) SOLD			TEST WITNESSED BY
35. LIST OF ATTACHMENTS WELBORE SCHEMATIC & PERFORATION DETAIL ATTACHMENT PAGE 1			
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records			
SIGNED JIM SIMONTON		COMPLETION SUPERVISOR	

(See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CONFIDENTIAL



37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.
UINTA	SURFACE		
GREEN RIVER	1630'		
WASATCH	4370'		
MESA VERDE	6280'		
TD	8325'		

38. GEOLOGIC MARKERS
RWS 12 ML 6 9 24

NAME	TOP	
	MEAS. DEPTH	TRUE VERT. DEPTH
UINTA	SURFACE	
GREEN RIVER	1630'	
WASATCH	4370'	
MESA VERDE	6280'	
TD	8325'	

CONFIDENTIAL

RWS 12ML 6 9 24 – ATTACHMENT PAGE 1

PERFORATION DETAIL:

<u>Open Perfs</u>	<u>Stimulation</u>					<u>Perf Status</u>
4815' – 4819' }	Frac w/	100,480	Lbs in	38,388	Gals	Open - Wasatch
4884' – 4888' }						Open - Wasatch
5072' – 5080' }						Open - Wasatch
5331' – 5335' }	Frac w/	79,300	Lbs in	35,910	Gals	Open - Wasatch
5356' – 5362' }						Open - Wasatch
5366' – 5372' }						Open - Wasatch
5946' – 5956' }	Frac w/	49,500	Lbs in	21,714	Gals	Open - Wasatch
6042' – 6048' }						Open - Wasatch
7464' – 7468' }	Frac w/	48,500	Lbs in	87,990	Gals	Open - LMV
7514' – 7518' }						Open - LMV
7548' – 7552' }						Open - LMV

CONFIDENTIAL

FIELD: Red Wash South		GL: 5039' KBE: 5051'	Spud Date: 1/24/07 Completion Date: 3/1/07																																																									
Well: RWS 12ML 6 9 24		TD: 8325' P8TD: 8211'	Current Well Status: Flowing Gas Well																																																									
Location: NWSW Sec 6-T9S-R24E 2180' FSL, 698' FWL Uintah County, Utah		API#: 43-047-37312																																																										
<div><div>Wellbore Schematic</div><div><div><div>Surface casing</div><div>Size: 9-5/8"</div><div>Weight: 36#</div><div>Grade: J-55</div><div>Cmtd w/ 835 sxs</div><div>Hole size: 12-1/4"</div><div>Set @ 2244' KB</div></div><div><div>EXCLUDED PERFS</div></div><div><div>TOC @ 350'</div><div>OPEN PERFS</div><div>4815' - 4819' Wasatch</div><div>4884' - 4888' Wasatch</div><div>5072' - 5080' Wasatch</div><div>5331' - 5335' Wasatch</div><div>5356' - 5362' Wasatch</div><div>5366' - 5372' Wasatch</div><div>5946' - 5956' Wasatch</div><div>6042' - 6048' Wasatch</div><div>F Nipple @ 7357</div><div>EOT @ 7390</div><div>7464' - 7468' LMV</div><div>7514' - 7518' LMV</div><div>7548' - 7552' LMV</div><div>P8TD @ 8211'</div><div>TD @ 8325'</div></div></div></div> <div><div>Tubing Landing Detail:</div><table><tr><td>Description</td><td>Size</td><td>Footage</td><td>Depth</td></tr><tr><td>KB</td><td></td><td>12.00</td><td>12.00</td></tr><tr><td>Hanger</td><td>2 3/8"</td><td>0.85</td><td>12.85</td></tr><tr><td>230 Jts 2-3/8" Tbg</td><td>2 3/8"</td><td>7,343.56</td><td>7,356.41</td></tr><tr><td>"F" Nipple 1.81"</td><td>2 3/8"</td><td>0.91</td><td>7,357.32</td></tr><tr><td>1 Jt 2-3/8" Tbg</td><td>2 3/8"</td><td>31.67</td><td>7,388.99</td></tr><tr><td>Shear Sub</td><td>2 3/8"</td><td>0.91</td><td>7,389.90</td></tr><tr><td>EOT @</td><td></td><td></td><td>7,389.90</td></tr></table><div><div>TUBING INFORMATION</div><div>Condition:</div><div>New: <input checked="" type="checkbox"/> Used: Rerun: </div><div>Grade: J-55 EUE 8rd</div><div>Weight (#/ft): 4.7#</div><div><div>Sucker Rod Detail:</div><table><tr><td>Size</td><td>#Rods</td><td>Rod Type</td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table><div><div>Rod Information</div><div>Condition:</div><div>New: Used: Rerun: </div><div>Grade: </div><div>Manufacture: </div><div><div>Pump Information:</div><div>API Designation</div><div>Example: 25 x 150 x RHAC X 20 X 6 X 2</div><div>Pump SN#: Original Run Date: </div><div>RERUN NEW RUN </div><div><div>ESP Well</div><div>Cable Size: </div><div>Pump Intake @ </div><div>End of Pump @ </div><div><div>Flowing Well</div><div>SN @ 7356'</div><div>PKR @ </div><div>EOT @ 7390'</div></div></div><div><div>Wellhead Detail:</div><div>Example: 7-1/16" 3000#</div><div></div><div></div><div></div><div>Other: </div><div>Hanger: Yes <input checked="" type="checkbox"/> No </div></div><div><div>SUMMARY</div><div>Zone #1- Frac LMV F/ 7464' - 7552' w/ 48,500# 20/40 mesh sand</div><div>Zone #2 - Frac Wasatch F/ 5946' - 6048' w/ 49,500# 20/40 mesh sand</div><div>Zone #3 - Frac Wasatch F/ 5331' - 5372' w/ 79,300# 20/40 mesh sand</div><div>Zone #4 - Frac Wasatch F/ 4815' - 5080' w/ 100,480# 20/40 mesh sand</div><div>DOFP - 3/1/07</div></div></div></div><div><div>Production Casing</div><div>Size: 4-1/2"</div><div>Weight: 11.6#</div><div>Grade: M-80</div><div>Cmtd w/ 1460 sxs</div><div>Set @ 8325'</div><div>Hole size: 7-7/8"</div></div></div><div><div>Prepared By: Dahn Caldwell</div><div>Date: 5/1/07</div></div></div><div data-bbox="1013 2486 1321 2556" data-label="Text"><p>CONFIDENTIAL</p></div></div>					Description	Size	Footage	Depth	KB		12.00	12.00	Hanger	2 3/8"	0.85	12.85	230 Jts 2-3/8" Tbg	2 3/8"	7,343.56	7,356.41	"F" Nipple 1.81"	2 3/8"	0.91	7,357.32	1 Jt 2-3/8" Tbg	2 3/8"	31.67	7,388.99	Shear Sub	2 3/8"	0.91	7,389.90	EOT @			7,389.90	Size	#Rods	Rod Type																					
Description	Size	Footage	Depth																																																									
KB		12.00	12.00																																																									
Hanger	2 3/8"	0.85	12.85																																																									
230 Jts 2-3/8" Tbg	2 3/8"	7,343.56	7,356.41																																																									
"F" Nipple 1.81"	2 3/8"	0.91	7,357.32																																																									
1 Jt 2-3/8" Tbg	2 3/8"	31.67	7,388.99																																																									
Shear Sub	2 3/8"	0.91	7,389.90																																																									
EOT @			7,389.90																																																									
Size	#Rods	Rod Type																																																										



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov/ut/st/en.html>



IN REPLY REFER TO
3180
UT-922

May 25, 2010

Birgit Roesink-Miller
Questar Exploration & Production Co.
1050 17th Street, Suite 500
Denver, CO 80265

Re: Initial Consolidated Wasatch-Mesaverde-
Mancos-Dakota Formation PA
Big Valley Unit
Uintah County, Utah

Dear Mrs. Roesink-Miller:

The Initial Consolidated Wasatch-Mesaverde-Mancos-Dakota Formation PA, Big Valley Unit, CRS No. UTU81308C, is hereby approved effective as of December 1, 2006, pursuant to Section 11 of the Big Valley Unit Agreement, Uintah County, Utah.

The Initial Consolidated Wasatch-Mesaverde-Mancos-Dakota Formation PA results in an initial consolidated participating area of 3,780.63 acres and is based upon the completion of the following wells as capable of producing unitized substances in paying quantities.

WELL NO.	API NO.	LOCATION	LEASE NO.
RWS 16ML-6-9-24	43-047-37335	SE¼SE¼, 06-9S-24E	UTU73456
RWS 2ML-5-9-24	43-047-37306	NW¼NE¼, 05-9S-24E	UTU73456
→ RWS 12ML-6-9-24	43-047-37312	NW¼SW¼, 06-9S-24E	UTU73456
RWS 4ML-5-9-24	43-047-37351	NW¼NW¼, 05-9S-24E	UTU73456
RWS 4ML-6-9-24	43-047-37412	NW¼NW¼, 06-9S-24E	UTU73456
RWS 8D-6-9-24	43-047-37352	SE¼NE¼, 06-9S-24E	UTU73456
RWS 6D-5-9-24	43-047-37350	SE¼NW¼, 05-9S-24E	UTU73456
RWS 6D-6-9-24	43-047-37413	SE¼NW¼, 06-9S-24E	UTU73456
NBZ 8D-31-8-24	43-047-37238	SE¼NE¼, 31-8S-24E	UTU77301
CWD 10D-32-8-24	43-047-37347	NW¼SE¼, 32-8S-24E	UTU78029
CWD 14D-32-8-24	43-047-37277	SE¼SW¼, 32-8S-24E	UTU78029

RECEIVED

JUN 07 2010

The following wells not capable of producing unitized substances in paying quantities will be included in the Initial Consolidated Wasatch-Mesaverde-Mancos-Dakota Formation PA pursuant to Section 11 of the unit agreement as necessary for unit operations.

WELL NO.	API NO.	LOCATION	LEASE NO.
RWS 10ML-5-9-24	43-047-37308	NW¼SE¼, 05-9S-24E	UTU73456
RWS 14D-5-9-24	43-047-37310	SE¼SW¼, 05-9S-24E	UTU73456
RWS 14D-6-9-24	43-047-37414	SE¼SW¼, 06-9S-24E	UTU73456
NBZ 8ML-30-8-24	43-047-37231	SE¼NE¼, 30-8S-24E	UTU77301
NBZ 13ML-29-8-24	43-047-37237	SW¼SW¼, 29-8S-24E	UTU77301
CWD 16D-32-8-24	43-047-37278	SE¼SE¼, 32-8S-24E	UTU78029

Copies of the approved request are being distributed to the appropriate Federal agencies and one copy is returned herewith. Please advise all interested parties of the approval of the Initial Consolidated Wasatch-Mesaverde-Mancos-Dakota Formation PA, Big Valley Unit, and the effective date.

No action will be taken at this time to your request for the contraction of the Big Valley Unit as it will automatically contract June 16, 2010.

Sincerely,

/s/ Roger L. Bankert

Roger L. Bankert
Chief, Branch of Minerals

Enclosure

bcc: UDOGM
SITLA
MMS - MRM w/enclosure (Attn: Leona Reilly)
FOM - Vernal w/enclosure
Unit file - Big Valley w/enclosure
Fluids - Mickey
Fluids - Judy
Agr. Sec. Chron.
Reading File
Central Files

LWilcken:lw:(05/25/10)

RECEIVED
JUN 07 2010
DIV. OF OIL, GAS & MINING

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET (for state use only)

ROUTING
 CDW

Change of Operator (Well Sold)

X - Operator Name Change

The operator of the well(s) listed below has changed, effective:

6/14/2010

FROM: (Old Operator): N5085-Questar Exploration and Production Company 1050 17th St, Suite 500 Denver, CO 80265 Phone: 1 (303) 308-3048	TO: (New Operator): N3700-QEP Energy Company 1050 17th St, Suite 500 Denver, CO 80265 Phone: 1 (303) 308-3048
----------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------

CA No.				Unit:		BIG VALLEY		
WELL NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED								

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 6/28/2010
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 6/28/2010
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 6/24/2010
- a. Is the new operator registered in the State of Utah: Business Number: 764611-0143
- a. (R649-9-2) Waste Management Plan has been received on: Requested
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 8/16/2010 BIA not yet
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: 8/16/2010
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to **Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 6/29/2010

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 6/30/2010
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 6/30/2010
- Bond information entered in RBDMS on: 6/30/2010
- Fee/State wells attached to bond in RBDMS on: 6/30/2010
- Injection Projects to new operator in RBDMS on: 6/30/2010
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: ESB000024
- Indian well(s) covered by Bond Number: 965010693
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 965010695
- b. The **FORMER** operator has requested a release of liability from their bond on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1 TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER _____

2 NAME OF OPERATOR:
Questar Exploration and Production Company *N5085*

3 ADDRESS OF OPERATOR:
1050 17th Street, Suite 500 CITY Denver STATE CO ZIP 80265 PHONE NUMBER: (303) 672-6900

4 LOCATION OF WELL

FOOTAGES AT SURFACE: See attached

COUNTY: Attached

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

11 CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>6/14/2010</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Operator Name Change</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective June 14, 2010 Questar Exploration and Production Company changed its name to QEP Energy Company. This name change involves only an internal corporate name change and no third party change of operator is involved. The same employees will continue to be responsible for operations of the properties described on the attached list. All operations will continue to be covered by bond numbers:

Federal Bond Number: 965002976 (BLM Reference No. ESB000024)

Utah State Bond Number: ~~965003033~~

Fee Land Bond Number: ~~965003033~~ } *965010695*

BIA Bond Number: ~~799446~~ *965010693*

The attached document is an all inclusive list of the wells operated by Questar Exploration and Production Company. As of June 14, 2010 QEP Energy Company assumes all rights, duties and obligations as operator of the properties as described on the list

NAME (PLEASE PRINT) Morgan Anderson

TITLE Regulatory Affairs Analyst

SIGNATURE

DATE 6/23/2010

(This space for State use only)

RECEIVED

JUN 28 2010

DIV. OF OIL, GAS & MINING

(See Instructions on Reverse Side)

APPROVED *6/30/2009*

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

Questar Exploration Production Company (N5085) to QEP Energy Company (N3700)
BIG VALLEY
effective June 14, 2010

well_name	sec	tpw	rng	api	entity	mineral lease	type	stat	C
RWS 3ML-9-9-24	09	090S	240E	4304735483	15190	Federal	GW	S	
RWS 10ML-6-9-24	06	090S	240E	4304735653	17644	Federal	GW	P	
CWD 4ML-32-8-24	32	080S	240E	4304735684	17644	Federal	GW	S	
NBZ 4D-30-8-24	30	080S	240E	4304737229	16630	Federal	GW	OPS	C
NBZ 6ML-30-8-24	30	080S	240E	4304737230	16810	Federal	GW	OPS	C
NBZ 8ML-30-8-24	30	080S	240E	4304737231	17644	Federal	GW	P	
NBZ 10ML-30-8-24	30	080S	240E	4304737232	16695	Federal	GW	OPS	C
NBZ 12D-30-8-24	30	080S	240E	4304737233	16631	Federal	GW	OPS	C
NBZ 14ML-30-8-24	30	080S	240E	4304737234	16696	Federal	GW	OPS	C
NBZ 6D-31-8-24	31	080S	240E	4304737235	16611	Federal	GW	OPS	C
NBZ 4D-31-8-24	31	080S	240E	4304737236	16576	Federal	GW	OPS	C
NBZ 13ML-29-8-24	29	080S	240E	4304737237	17644	Federal	GW	P	
NBZ 8D-31-8-24	31	080S	240E	4304737238	17644	Federal	GW	P	
NBZ 2ML-31-8-24	31	080S	240E	4304737239	17098	Federal	GW	OPS	C
NBZ 11D-29-8-24	29	080S	240E	4304737240	16612	Federal	GW	OPS	C
NBZ 5D-29-8-24	29	080S	240E	4304737241	16632	Federal	GW	OPS	C
NBZ 9D-29-8-24	29	080S	240E	4304737244	15677	Federal	GW	OPS	C
NBZ 15ML-29-8-24	29	080S	240E	4304737246	16697	Federal	GW	OPS	C
CWD 3D-32-8-24	32	080S	240E	4304737274	16923	Federal	GW	OPS	C
CWD 14ML-32-8-24	32	080S	240E	4304737277	17644	Federal	GW	P	
CWD 16D-32-8-24	32	080S	240E	4304737278	17644	Federal	GW	P	
RWS 2ML-5-9-24	05	090S	240E	4304737306	17644	Federal	GW	P	
RWS 8D-5-9-24	05	090S	240E	4304737307	16614	Federal	GW	OPS	C
RWS 10ML-5-9-24	05	090S	240E	4304737308	17644	Federal	GW	S	
RWS 12ML-5-9-24	05	090S	240E	4304737309	17644	Federal	GW	P	
RWS 14D-5-9-24	05	090S	240E	4304737310	17644	Federal	GW	P	
RWS 16ML-5-9-24	05	090S	240E	4304737311	16698	Federal	GW	OPS	C
RWS 12ML-6-9-24	06	090S	240E	4304737312	17644	Federal	GW	P	
RWS 16ML-6-9-24	06	090S	240E	4304737335	17644	Federal	GW	P	
CWD 10D-32-8-24	32	080S	240E	4304737347	17644	Federal	GW	P	
RWS 6D-5-9-24	05	090S	240E	4304737350	17644	Federal	GW	P	
RWS 4ML-5-9-24	05	090S	240E	4304737351	17644	Federal	GW	P	
RWS 8D-6-9-24	06	090S	240E	4304737352	17644	Federal	GW	P	
RWS 2D-6-9-24	06	090S	240E	4304737411	17272	Federal	GW	OPS	C
RWS 4ML-6-9-24	06	090S	240E	4304737412	17644	Federal	GW	S	
RWS 6D-6-9-24	06	090S	240E	4304737413	17644	Federal	GW	P	
RWS 14D-6-9-24	06	090S	240E	4304737414	17644	Federal	GW	P	
RWS 5ML-9-9-24	09	090S	240E	4304738645	17273	Federal	GW	OPS	C
RWS 12ML-9-9-24	09	090S	240E	4304738646	17274	Federal	GW	OPS	C
NBZ 16D-31-8-24	31	080S	240E	4304739435		Federal	GW	APD	C
NBZ 10D-31-8-24	31	080S	240E	4304739456		Federal	GW	APD	C
NBZ 12D-31-8-24	31	080S	240E	4304739457		Federal	GW	APD	C
NBZ 14D-31-8-24	31	080S	240E	4304739458		Federal	GW	APD	C
CWD 13D-32-8-24	32	080S	240E	4304739464		Federal	GW	APD	C
RWS 7D-6-9-24	06	090S	240E	4304739494		Federal	GW	APD	C
RWS 13D-6-9-24	06	090S	240E	4304739495		Federal	GW	APD	C
RWS 11D-6-9-24	06	090S	240E	4304739496		Federal	GW	APD	C
RWS 9D-6-9-24	06	090S	240E	4304739497		Federal	GW	APD	C
RWS 3D-6-9-24	06	090S	240E	4304739498		Federal	GW	APD	C
RWS 15D-6-9-24	06	090S	240E	4304739500		Federal	GW	APD	C

Bonds: BLM = ESB000024
BIA = 956010693
State = 965010695

Questar Exploration Production Company (N5085) to QEP Energy Company (N3700)
BIG VALLEY
effective June 14, 2010

well_name	sec	twp	rng	api	entity	mineral lease	type	stat	C
RWS 5D-6-9-24	06	090S	240E	4304739501		Federal	GW	APD	C
RWS 7D-5-9-24	05	090S	240E	4304739502		Federal	GW	APD	C
RWS 11D-5-9-24	05	090S	240E	4304739503		Federal	GW	APD	C
RWS 9D-5-9-24	05	090S	240E	4304739504		Federal	GW	APD	C
RWS 13D-5-9-24	05	090S	240E	4304739505		Federal	GW	APD	C
RWS 15D-5-9-24	05	090S	240E	4304739506		Federal	GW	APD	C
RWS 3D-5-9-24	05	090S	240E	4304739507		Federal	GW	APD	C
RWS 1D-5-9-24	05	090S	240E	4304739508		Federal	GW	APD	C
NBZ 5D-31-8-24	31	080S	240E	4304739511		Federal	GW	APD	C
CWD 11D-32-8-24	32	080S	240E	4304739535		Federal	GW	APD	C
CWD 15D-32-8-24	32	080S	240E	4304739536		Federal	GW	APD	C
RWS 5D-5-9-24	05	090S	240E	4304739673		Federal	GW	APD	C
RWS 1D-6-9-24	06	090S	240E	4304739674		Federal	GW	APD	C
NBZ 3D-31-8-24	31	080S	240E	4304739675		Federal	GW	APD	C
NBZ 16D-30-8-24	30	080S	240E	4304740355		Federal	GW	APD	C
NBZ 15D-30-8-24	30	080S	240E	4304740356		Federal	GW	APD	C
CWD 6D-32-8-24	32	080S	240E	4304740357		Federal	GW	APD	C
CWD 2D-32-8-24	32	080S	240E	4304740358		Federal	GW	APD	C
CWD 5D-32-8-24	32	080S	240E	4304740359		Federal	GW	APD	C
NBZ 10D-29-8-24	29	080S	240E	4304740360		Federal	GW	APD	C
NBZ 8D-29-8-24	29	080S	240E	4304740361		Federal	GW	APD	C
NBZ 14D-29-8-24	29	080S	240E	4304740362		Federal	GW	APD	C
NBZ 16D-29-8-24	29	080S	240E	4304740363		Federal	GW	APD	C
NBZ 12D-29-8-24	29	080S	240E	4304740364		Federal	GW	APD	C
NBZ 13D-30-8-24	30	080S	240E	4304740365		Federal	GW	APD	C
RWS 4D-9-9-24	09	090S	240E	4304740470		Federal	GW	APD	C
NBZ 9D-30-8-24	30	080S	240E	4304740471		Federal	GW	APD	C
NBZ 11D-30-8-24	30	080S	240E	4304740472		Federal	GW	APD	C
NBZ 7D-30-8-24	30	080S	240E	4304740473		Federal	GW	APD	C
NBZ 2D-29-8-24	29	080S	240E	4304740476		Federal	GW	APD	C
CWD 7D-32-8-24	32	080S	240E	4304740477		Federal	GW	APD	C
CWD 9D-32-8-24	32	080S	240E	4304740478		Federal	GW	APD	C
RWS 6D-9-9-24	09	090S	240E	4304740479		Federal	GW	APD	C
RWS 13D-9-9-24	09	090S	240E	4304740480		Federal	GW	APD	C
NBZ 6D-29-8-24	29	080S	240E	4304740483		Federal	GW	APD	C
NBZ 1D-30-8-24	30	080S	240E	4304740484		Federal	GW	APD	C
NBZ 2D-30-8-24	30	080S	240E	4304740485		Federal	GW	APD	C
NBZ 3D-30-8-24	30	080S	240E	4304740486		Federal	GW	APD	C



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, UT 84145-0155

<http://www.blm.gov/ut/st/en.html>



IN REPLY REFER TO:

3100

(UT-922)

JUL 28 2010

Memorandum

To: Vernal Field Office, Price Field Office, Moab Field Office

From: Chief, Branch of Minerals

Roger L Bankert

Subject: Name Change Recognized

Attached is a copy of the Certificate of Name Change issued by the Texas Secretary of State and a decision letter recognizing the name change from the Eastern States Office. We have updated our records to reflect the name change in the attached list of leases.

The name change from **Questar Exploration and Production Company** into **QEP Energy Company** is effective June 8, 2010.

cc: MMS
UDOGM

RECEIVED

AUG 16 2010

DIV. OF OIL, GAS & MINERALS